




CRANE BRIDGE – TOP VIEW


CRANE BRIDGE, HOIST AND MOTORS – NOT IN MAIMAAR SCOPE (BY OTHERS)






CRANE BEAM - SECTION, ELEVATION AND RAIL

PLATE SIZES READ OFF THE MSPL-032 SINGLE-PART SHEET (MAIMAAR FACTORY, 10 MT)





CAPACITY 10 MT - BSF MSPL-26-276, AREA 5172
SPAN 17690 C/C OF RUNWAY BEAMS - BSF ; RUNWAY LENGTH 30,480
HOOK HEIGHT 6,000 FFL TO HOOK - BSF ; SERVICE CLASS C, LOADING CATEGORY 3
LOADS 84 VERTICAL / 11 HORIZONTAL - BSF ; MAKE: KONE, TOP RUNNING, PENDANT
BUILDING 30,480 X 18,290, EAVE 10,670, BAYS 1@7,240 + 2@8,000 + 1@7,240 - BSF
SECTION SOURCE THE CRANE BEAM PLATES ARE MSPL-032'S, NOT THIS JOB'S - SEE SHEET 3
TYPE TOP RUNNING (TR) - MANUAL CH.8 LISTS TR / MONORAIL / UNDERHUNG / JIB / SEMI-GANTRY
END CARRIAGE WHEELS 2 PER END, 4 TOTAL - MANUAL CH.8 NWB = 2 (WORKED 10 MT EXAMPLE)
WHEEL 100 HIGH X 18 WIDE; 15 LAPS DOWN ONTO THE RAIL - OWNER, 5-SEP-2026
18 OF OPEN GAP ABOVE THE RAIL, THEN 67 INSIDE THE CARRIAGE - THE 67 IS DERIVED
(THE GH CATALOGUE BAND WOULD GIVE 250 AT 10 MT - THE MEASURED FIGURE IS USED)
RUNWAY TOLERANCE RAIL TO WEB ECCENTRICITY $\leq 0.75 \times \text{WEB THICKNESS}$ - CMAA/AISC
END CARRIAGE WELDED BOX, WHEELS ON THE BOTTOM; THE BRIDGE JUST RESTS ON TOP
200 X 200 SQUARE BOX, 1500 LONG, UNDER A 1000-1400 GIRDER - OWNER, 5-SEP-2026
WHEEL BASE 1200, FROM A 1500 CARRIAGE LESS 150 EACH END - OWNER
NOTE THE LIVE BSF (MSPL-26-276) CARRIES 3,900 ; CMAA GUIDANCE IS $\geq \text{SPAN}/7 = 3,048$

A SHORT WHEEL BASE UNDER A LONG SPAN IS WHAT LETS A CRANE SKEW ON ITS RUNWAY
STACK TOR -15 WHEEL BOTTOM / 0 RAIL / +18 BOX SOFFIT / +85 WHEEL TOP / +218 BOX TOP
VERTICAL IMPACT 10% PENDANT OPERATED - MANUAL TABLE 8.3
CMAA SERVICE CLASS C - MANUAL TABLE 8.1
LONGITUDINAL 10% OF MAX WHEEL LOAD, AT TOP OF RAILS - MANUAL CH.8 SEC 2.4.4
RUNWAY BEAM BUILT-UP, DOUBLE SIDE FILLET WELD (≤ 15 MT) - THAL 125-23 SPEC
SCOPE IS SAID BY THE LABEL, NOT BY THE LINETYPE - REF: CRANE-IN-PEB-SECTION
HOOK HEIGHT FFL-TO-HOOK SETS THE EAVE HEIGHT - MANUAL, EAVE HEIGHT GUIDELINE
GIRDER DEPTH $(500 + \text{SPAN}/30.5) \times (\text{CAP}/10)^{0.20}$ - 1000 AT 15,240 SPAN, 1200 AT 21,335
GIRDER END ONE TAPERED CUT TO A 400 DEEP STUB ~400 LONG, RESTING ON THE END CARRIAGE
CRANE BEAM BAY/15 $\times (\text{CAP}/10)^{0.25}$, SNAPPED TO 25 ; 400 WEB AT A 6,096 BAY, 10 MT
CRANE BEAM PLATES WEB PL 8 X 400 / FLANGE PL 10 X 225 / STIFFENER FL 8 X 108
MSPL-032 SINGLE PARTS: CRB-1,2 X4 EACH ; OF33,34,35,37 X4 EACH ; ST4 X128
 $(225 - 8) / 2 = 108$ - THE STIFFENER CONFIRMS BOTH THE FLANGE AND THE WEB
GIRDER 1000 DEEP AT 50 FT (15,240) SPAN, 10 MT - MAIMAAR PRODUCTION, 2026