

Quotation For Interior Work

Sr.#	Description of Work	Unit	Qty	Unit Rate	Amount	Remarks
1	Providing and Laying first class solid burnt brick masonry set in cement mortar 1: 6 in straight or curved walls 4-1/2 inch, 9-inch thick complete in top floor and etc. complete in all respect as per direction by Engineer Incharge.	CFT	270	403	108,675	
2	Providing & laying ½ inch (19 mm) thick cement plaster 1:4 on walls etc. including making edges, corners, comers, and curing etc. complete in all respect as per direction by Engineer Incharge.	Sq. Ft	850	52	43,988	
3	Orividing & laying paint SPD Berger or equivalent including wall putty filling etc complete in all respect as per direction of Engineer Incharge.	Sq. Ft	850	52	43,988	
4	Providing and laying in situ 1:4:8 (1 cement 4 sand and 8 coarse aggregate) cement concrete 2" thick using screened graded bajri 3/4 inch and down gauge in top floor under tile i/c compacting, curing, cost of form work and its removal etc. complete in all respect as per direction of Engineer Incharge.	Sq. Ft	1,377	115	158,355	
5	Providing and laying coloured/ glazed/ ceramic/porcelain tiles MASTER BRAND size up-to 18"x18". on walls and floors of approved size and colour set in neat cement and joints grouted with white/coloured cement using imported pigments over and including 1/2" thick 1:4 cement sand plaster base, including cutting, complete.	Sq. Ft	1,500	403	603,750	
6	Providing and fixing powder coated aluminum windows/ventilators with large spans premium model (of approved colour) with fixed/sliding openable window/Fly screen shutter, using 2-mm thick minimum aluminum sections with minimum 100-mm wide frame, including 5-mm thick imported/Ghani glass single glazed glass, strengthing /fixing arrangements, fixed with stainless steel screws, stiffer bracket, sealing the joints between aluminum sections and adjoining surfaces with transparent silicon sealant both inside and outside, etc. complete in all respect as per approved design.	Sq. Ft	200	978	195,500	
6	Providing hollow flush doors with 4-1/2" walls 1-1/2" thick single or double leaf flush shutters with solid core (Kail wood) and 4 mm (minimum) thick commercial play hydraulically pressed on both sides (wherever specified with approved design of grooves, wood architraves/ beads/lipping to shutters,locks and all hardware fittings, matt enamel painting/polishing , complete in all respects as per direction of engineer incharge.	Sq. Ft	300	1,610	483,000	
Total Amount for Civil Works (A)					1,637,255	
Plumbing Works						
	General Notes: Supply, Installation, Testing and Commissioning of the following items of works including all Material, Labour, Plants, Accessories etc. required for proper completion of each item as per direction of Engineer Incharge.					
Sr.#	Description of Work	Unit	Qty	Unit Rate	Amount	Remarks
1	PPR water pipes (cold and hot) inside building & in ducts (un-exposed to sunlight conditions) conforming to DIN 8077-78, I/C all fittings, cutting, jointing, making holes in concrete or masonry and then repairing holes, supports and hangers etc. Master fit make or equivalent of the following diameters.					
	a. 40mm	RFT.	150	345	51,750	
	b. 32mm	RFT.	65	253	16,445	
	c. 25mm	RFT.	200	196	39,100	
2	UPVC Soil, Waste, and vent pipes pressure pipe class "B" of the following diameters, including imported rubber ring fittings, jointing, cutting, and breaking concrete and then making it good, applying protective painting, coating, cleaning and testing etc, complete in all respects. (make MASTER Fit or equivalent).					
	a. 2 inch dia.	RFT.	30	201	6,038	
	b. 3 inch dia.	RFT.	100	288	28,750	
	c. 4 inch dia.	RFT.	300	403	120,750	
3	Best quality water closet apparatus European (W.C) medium size make ICL, Porta, include WC cover with brass oxidized bolts kit, themle export quality, rubber connection etc. (of not less than 18 inches clear opening as measured between flushing rims) complete with and i/c the cost of 13.6 litre best quality low level plastic flushing cistern with internal fittings complete P.V.C flushing pipe suitable for squertting type with extra bends and length with fittings, floor trap 4 inches (100mm) dia and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1:2:4 etc. complete in all respect as per direction of Engineer Incharge.	Nos.	3	40,250	120,750	