
SECTION 1: SCOPE OF WORKS

1.1 Supply of Materials By: Existing Supplied Doors By Mammut Building Systems

Maimaar Engineers & Contractors scope of work is to remove the existing doors & re-fix the same at new location

1.2 Casting of Anchor Bolts (Civil Contractor):

Not applicable

1.3 Reference Documents:

- Supplier erection drawings for shutter doors
- Site visit

1.4 Supply of Services by Maimaar Engineers & Contractors:

Maimaar Engineers & Contractors are to provide complete services for removal of existing Roll-up shutter doors & re-fix on new location using

- Scaffolding with ladder access
- Chain Blocks
- Adjustable Wrench
- 1/2" drive socket set
- Leveling device
- Rope pulleys
- Grinder
- Drill machine
- PPE's for all workers (Safety Shoes, Helmets, Safety Harnesses)
- Life line
- All others tools required for removal & re-fixing of shutter doors