



SECTION 1: SUPPLY AND ERECTION PRICE

1.1 Total Supply and Erection Price

Design, Fabrication, Transportation, Erection:				
Description	Unit	Quantity	Unit Price (PKR)	Price (PKR)
Design, Fabrication, Transportation, Erection of MS-Lift Structure of height 19.401m using Steel Tubes of size 125x125x7-8 (H-Section), including C-Channels for Deck Panel Platforms. MS material 7,500-8000 Kgs (Estimated) Including primer paint, final coat, connections plates, connections bolts, supporting members for lift Installation, Door Openings Framing, Connections with Existing Structure, on site welding including the scaffolding for the Installation of LIFT & MS Structure. (Design is not by Maimaar)	LS	01	3,960,000	3,960,000
PPGL Liner in Lift & Machine Room - 362 Sq. Ft Fiberglass Insulation for Machine Room - 240 Sq. Ft PIR Sandwich Panel for Roof - 165 Sq. Ft Aluminum Doors 8'x3' - 4 No's	LS	01	1,076,815	1,076,815
Supply & fixing of 12mm Cement Board including the framing consistent of Hollow MS Tube (16 Gauge-1.50"x1.50") Mesh (@ 18"x18" c/c horizontally and vertically) all around	Sq. Ft	2,250	1,175	2,643,750
Civil Works for the lift structure 250-300 Cu. Ft Concrete Including excavation and Steel Bars	LS	01	1,200,000	1,200,000
Price (Rs.) – Exclusive of all Taxes				8,880,565
18% GST				1,598,502
Total Price – Inclusive of All Taxes				10,479,067

1. Prices are Inclusive of all Taxes.
2. Any additional area will be charged separately.
3. Incase design is not passed on above given sections in drawings, we may revise the prices accordingly.

SECTION 2: PAYMENT TERMS

8.1 Payment Terms

- **50%** as an Advance at the time of Placement of the Order.
- **45%** before the delivery of materials.
- **05%** upon completion of the project.